

STA. NO.	PROCESS NAME	TIME IN MIN'S	SPACING BET'N TANK	ID D.O.T	TANKS SIZES IN C.D.O.T.	INCHES DEPTH	LIPS DOT	LIPS CDOT	LINING MATERIAL	DTO DIM	DRAIN DATA	HOOD MATL	OPER TEMP	TEMP CONT	COIL. TYPE	BUSSING AMPERES	AUXILIARY EQUIPMENT	AGIT-ATION
1	LIFTING LOAD		0.00	32.00	76.00	64.00	2.00	2.00	2 x 2	TUBULAR	STEEL	CONSTRUC-	TION,	S.BLASTED	PRIMED,	PAINTED	ELEVATOR LIFT	
2	TRANSFER SHUTTLE		50.00	32.00	76.00	64.00	2.00	2.00	2 x 2	TUBULAR	STEEL	CONSTRUC-	TION,	S.BLASTED	PRIMED,	PAINTED		
3-4	COUNTER F/RINSE		4.50	66.00	76.00	64.00	2.50	3.25	FRP	32x3x12" EXT. @4	2"							AIR
5	RACK STRIP		.50	32.00	76.00	64.00	2.50	3.25	304 SS	WELL 32x12xFULL		PVC PUSH PULL	120 F	BB	304 SS			MECH.
6-7	CONDI-TIONER #1		.50	62.00	76.00	64.00	2.50	3.25	316 SS	WELL 62x12xFULL	2"	PVC PUSH PULL	130 F	BB	316 SS		FILTER S.S.	AIR MECH.
8-9	RECLAIM		.50	66.00	76.00	64.00	2.50	3.25	FRP		2"							
10	CWR		.50	34.00	76.00	64.00	2.50	3.25	FRP	34x3x12" EXT.	2"							AIR
11	CONDI-TIONER #2		.50	34.00	76.00	64.00	2.50	3.25	316 SS	WELL 34x12xFULL	2"	PVC PUSH PULL	130 F	BB	316 SS		FILTER S.S.	AIR
12-13	RECLAIM		.50	66.00	76.00	64.00	2.50	3.25	FRP		2"							
14	CWR		.50	34.00	76.00	64.00	2.50	3.25	FRP	34x3x12" EXT.	2"							AIR
15-16	CAUSTIC ETCH		.50	62.00	76.00	64.00	2.50	3.25	M.S. INS.	WELL 62x12xFULL	2"	PVC PUSH PULL	185 F	BB	M.S.		FILTER CPVC	AIR MECH.
17-18	RECLAIM		.50	66.00	76.00	64.00	2.50	3.25	FRP		2"							
19	CWR		.50	34.00	76.00	64.00	2.50	3.25	FRP	34x3x12" EXT.	2"							AIR
20-22	CHROME ETCH		.50	96.00	76.00	64.00	2.50	3.25	FRP/TIT. INS.	WELL 96x12xFULL		PVC PUSH PULL	165 F	BB	TITANIUM		6x78x6" INT. WEIR	AIR
23	CWR		.50	34.00	76.00	64.00	2.50	3.25	FRP/KYNAR	34x3x12" EXT.	2"							AIR
24-27	COUNTER F/RINSE		.50	134.00	76.00	64.00	2.50	3.25	FRP	32x3x12" EXT. @24	2"							AIR
28	NEUTRAL-IZER #1		.50	34.00	76.00	64.00	2.50	3.25	PP/FRP/FOAM	WELL 34x12x36"	2"	PVC PUSH PULL	140 F	BB	TEFLON			AIR
29	NEUTRAL-IZER #2		.50	34.00	76.00	64.00	2.50	3.25	PP/FRP/FOAM	WELL 34x12x36"	2"	PVC PUSH PULL	140 F	BB	TEFLON			MECH.
30-32	COUNTER F/R TRIP		.50	100.00	76.00	64.00	2.50	3.25	FRP	32x3x12" EXT. @30	2"							AIR
33	WET SHUTTLE		2.00	34.00	224.00	64.00	4.50	3.25	FRP	SHUTTLE	CART,	TUBULAR	STEEL	CONSTRUC-	TION			

